

10-11
4-071008

176
R

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API number: 15-179-21,046-00-00
SW SE NW /4 SEC. 14, 09 S, 27 W
2970 feet from S section line
3630 feet from E section line

Operator license# 03655 Lease Popp well # 1

Operator: Staab Energy & Leasing County Sheridan

Address: 2514 Haney Drive Well total depth 4120 feet
Hays, Kansas 67601 Conductor Pipe: 0 inch @ 0 feet
Norman G. Staab Surface pipe 8 5/8 Inch @ 264 feet

133.90

Aband. oil well , Gas well , Input well , SWD , D & A

Plugging contractor: Shields Drilling Company, Inc. License# -

Address: Russell, Kansas 67665

Company to plug at: Hour: P.M. Day: 11 Month: October Year: 92

Plugging proposal received from: Bert Berry

Company: Shields Drilling Company, Inc. Phone: 913-628-1326

Were: 8 5/8" - 264' S.P. cwc. with 190 sx. - 2% gel. - 3% c.c.
Cemented by Allied Cementing. L.K.C. Well. No ar buckle. Elev. 2736'.
Anhy. 2332'. Mud condition - 50 vis. - 9.2 weight - 10-12 water loss.
No circulatin problems. Proposal 200 sx. 60/40 pozmix - 6% gel - 1 sx.
flocele. Spot with drill stem, circulate hole, heavy mud between all
plugs. 25 sx. cement @ 2340' - 100 sx. cement @ 1486' with 1 sx. flocele
mixed in - 10 sx. cement @ 40' - 15 sx. in rathole circulate - 10 sx.
in mousehole circulate.

Plugging Proposal Received by: Marion J. Schmidt
Plugging operations attended by agent? All[], Part[], None[]

Completed: Hour: 6:00P.M., Day: 11, Month: October, Year: 92

Actual plugging report: Shields ordered 200 sx. 60/40 pozmix - 6% gel.
and one sack of flocele. Spotted and displaced cement through drill
stem, circulated hole.

- 1st. plug @ 2340' w/25 sx. cement.
- 2nd. plug @ 1486' w/100 sx. cement and 1 sx. flocele.
- 3rd. plug @ 300' w/40 sx. cement.
- 4th. plug @ 40' w/10 sx. cement.
- 15 sx. in rathole (circulate) - 10 sx. in mousehole (circulate)

RECEIVED
STATE CORPORATION COMMISSION

OCT 26 1992
10-16-1992
CONSERVATION DIVISION
Wichita, Kansas

Remarks: Cemented by: Allied Cementing
Condition of casing(in hole): GOOD BAD Anhy.plug: YES NO
Bottom plug(in place): YES , CALC , NO Dakota plug: YES , NO
Plugged through TUBING , CASING . Elevation: 2736 GL

I did[] / did not[] observe the plugging.

INVOICED
DATE NOV 03 1992
INV. NO. 36659

Marion J. Schmidt
(agent)