

4-19

4-041667

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 S. MARKET, ROOM #2078
WICHITA, KANSAS 67202

API number: 15-179-21,022-00-00
SW NE NE /4 SEC. 16, 09 S, 27 W
4290 feet from S section line
990 feet from E section line

Operator license# 9860

Lease Popp well # 1

Operator: Castle Resources, Inc.

County Sheridan 134.88

Address: 1200 E. 27th Street
Hays, Kansas 67601

Well total depth 4150 feet
Conductor Pipe: 0 inch @ 0 feet
Surface pipe 8 5/8 Inch @ 258 feet
w/180 sxs.

Aband. oil well X, Gas well , Input well , SWD , D & A

Plugging contractor: Halliburton Cementing License#

Address: Hays, Kansas 67601

Company to plug at: Hour: 10:00A.M. Day: 19 Month: April Year: 95

Plugging proposal received from: Jerry Green

Company: Castle Resources, Inc. Phone:

Were: 4 1/2" casing set at 4136' w/475 sxs. cement. Anhy. @ 2311' with 400 sxs. W.L.M. 3950' - T.O.F. at 1500'.
Ordered 200 sxs. 60/40 pozmix - 10% gel with 1/4# F.C. plus 300# hulls plus 10 sxs. gel.

Plugging Proposal Received by: Dennis L. Hamel
Plugging operations attended by agent? All[], Part[X], None[]

Completed: Hour: 12:00P.M., Day: 19, Month: April, Year: 95

Actual plugging report: Hooked-up to 4 1/2" casing. Pumped down with 25 sxs. cement with 200# hulls, followed by 10 sxs. gel, followed with 150 sxs. cement with 100# hulls in cement. Max. P.S.I. 1000#. S.I.P. 1000#. Pressured-up annulus - no cement.

Remarks:
Condition of casing(in hole): GOOD X BAD Anhy. plug: YES X NO
Bottom plug(in place): YES , CALC X, NO Dakota plug: YES X, NO
Plugged through TUBING , CASING X. Elevation: GL

I did[X] / did not[] observe the plugging. Dennis L. Hamel
(agent)

Rec'd 4-28-95

HO

INVOICED

DATE 5-2-95
INV. NO. 42720