

4-071162

API Number: 15-179-21,078-00-00

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

12-22

SW SW SW /4 SEC. 16, 09 S, 27 W
330 feet from S section line
4950 feet from E section line

Operator license# 6040

Lease: Popp Well # 1

Operator: Bankoff Oil Company

County: Sheridan

Address: P.O. Box 16418
Wichita, Kansas 67216
J.E. Jespersen

Well total depth 4150 ^{134.88} feet
Conductor Pipe: 0 inch @ 0 feet
Surface pipe 8 5/8 Inch @ 297 feet

Aband. oil well, Gas well, Input well, SWD, D & A X

Plugging contractor: White & Ellis Drilling - Allied Cementing License# -

Address: Great Bend, Kansas 67530 - Russell, Kansas 67665

Company to plug at: Hour: P.M. Day: 22 Month: December Year: 1995

Plugging proposal received from: Judy

Company: White & Ellis Drilling Phone: 316-262-2984

Were: 8 5/8" - 297' S.P. cwc. w/200 sxs 60/40 pozmix - 2% gel - 4% c.c. By Allied Cementing. Elv. 2735' - Anhy. 2333' - No circulation problems. Proposal 190 sxs 60/40 pozmix - 6% gel and 1/4# flocele per sack - spot and displace all cement through drill pipe - heavy mud between all plugs. 25 sxs at 2340' - 100 sxs at 1480' - 40 sxs at 340' - 10 sxs at 40' - 15 sxs in rathole (circulate).

Plugging Proposal Received by: Marion J. Schmidt

Plugging operations attended by agent? All[], Part[], None[X]

Completed: Hour: 5:45 P.M., Day: 22, Month: December, Year: 1995

Actual plugging report: Bankoff ordered 190 sxs 60/40 pozmix - 6% gel - 1/4# flocele per sack - spotted and displaced all cement through drill stem with heavy mud between all plugs.

1st. Plug at 2340' w/25 sxs cement. Circulated hole mud vis. 42 - 45.
2nd. Plug at 1480' w/100 sxs cement.
3rd. Plug at 340' w/40 sxs cement.
4th. Plug at 40' w/10 sxs cement.
15 sxs in Rathole (circulated)

RECEIVED
KANSAS CORPORATION COMMISSION
01-03-1996
JAN 03 1996

Remarks: Cemented by Allied Cementing.
Condition of casing(in hole): GOOD BAD Anhy.plug: YES NO
Bottom plug(in place): YES, CALC, NO Dakota plug: YES X, NO
Plugged through TUBING, CASING. Elevation: GL

I did[] / did not[X] observe the plugging.

Marion J. Schmidt
(agent)

INVOICED
DATE 1-8-96
INV. NO. 44428
12-22

FEB 29 1996