

11-5

6-050096

TO: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

API number: 15-179-21,055-00-00

NW NW SE /4 SEC. 20, 9 S, 27 W  
2310 feet from S section line  
2310 feet from E section line

Operator license# 6111

Lease Kennedy well # 1

Operator: NB Company

County Sheridan

Address: P. O. Box 506  
Russell, Kansas

Well total depth 4190 feet  
Conductor Pipe:        inch @        feet  
Surface pipe 8 5/8 Inch @ 306 feet

136.18

Aband. oil well       , Gas well       , Input well       , SWD       , D & A X

Plugging contractor: Emphasis Drilling License# 8241

Address: Russell, Kansas

Company to plug at: Hour: 12:30 PM Day: 5 Month: November Year: 1992

Plugging proposal received from: Jack Fox

Company: Emphasis phone:       

Were: **Spot plugs through drill pipe w/ heavy mud between all plugs.**

1st plug @ 2370 feet with 25 sacks Rat hole: 15 sacks

2nd plug @ 1507 feet " 100 " Mousehole:        sacks

3rd plug @ 356 feet " 40 "

4th plug @ 40 feet " wiper plug & 10sx

Plugging Proposal Received by: Bruce D. Basye

Plugging operations attended by agent? All[        ], Part[        ], None[ X ]

Completed: Hour: 12:30 PM, Day: 5, Month: November, Year: 1992

Actual plugging report: Hole reported plugged as above.

Order 190 sx 60/40 pozmix w/ 6% gel and 2 sx celloflake or flowcel.

Remarks: Elevation: 2757 GL, Anhydrite depth: 2354 - 2392 feet

Did not penetrate Arbuckle, cemented by Allied

I did[        ] / did not[ X ] observe the plugging.

Bruce Basye  
Bruce D. Basye Geologist  
(agent)

Form CP-2/3

**INVOICED**

DATE 1-4-93

INV. NO. 37082