

4-050234

API Number: 15-179-21,084 -00-00

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

W2 E2 NE /4 SEC. 20 , 09 S, 27 W
3960 feet from S section line
990 feet from E section line

5-16

Operator license# 6037

Lease: Haffner Well # 1

Operator: Staab Oil Company

County: Sheridan

Address: 1607 Hopewell Road
Hays, Kansas 67601
913-625-5013

Well total depth 4155 ^{135.03} feet
Conductor Pipe: 0 inch @ 0 feet
Surface pipe 8 5/8 Inch @ 287 feet

Aband. oil well, Gas well, Input well, SWD, D & A X

Plugging contractor: Halliburton Services License#

Address:

Company to plug at: Hour: A.M. Day: 16 Month: May Year: 1996

Plugging proposal received from: Greg Davidson

Company: Phone:

Were: Order 190 sxs 60/40 pozmix - 6% gel - 1/4# Flo-seal per sack.
Elevation 2742'. Anhydrite 2345' - 2378'.

Plugging Proposal Received by: Marvin Miller

Plugging operations attended by agent? All [], Part [], None [X]

Completed: Hour 7:30 A.M. Day: 16 Month: May Year: 1996

Actual plugging report:

- 1st. Plug at 2360' with 25 sxs cement.
- 2nd. Plug at 1495' with 100 sxs cement.
- 3rd. Plug at 340' with 40 sxs cement.
- 4th. Plug at 40' with 10 sxs cement - 8 5/8" wiper plug.
- 15 sxs cement in rathole.

Remarks:

Condition of casing(in hole): GOOD BAD Anhy.plug: YES X NO

Bottom plug(in place): YES, CALC, NO Dakota plug: YES X, NO

Plugged through TUBING CASING Elevation: 2742 GL

I did [] did not [X] observe the plugging.

INVOICED

JUN 03 1996

Marvin Miller (agent)

Form CP-2/3

DATE JUN 12 1996

06-03-1996

CONSERVATION DIVISION WICHITA, KS

INV. NO. 45779