

2-26

4-031801

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API number: 15-179-21,063-00-00

C NW NW /4 SEC. 21, 09 S, 27 W
660 feet from S section line
660 feet from E section line

Operator license# 9482

Lease Whitmer well # 1

Operator: National Petroleum Reserves

County Sheridan 135.68

Address: 250 N. Rock Road
Suite 340
Wichita, Kansas 67206

Well total depth 4175 feet
Conductor Pipe: 0 inch @ 0 feet
Surface pipe 8 5/8 Inch @ 319 feet

Aband. oil well , Gas well , Input well , SWD , D & A

Plugging contractor: Emphasis Oil Operations License# 8241

Address: Box 506 - Russell, Kansas 67665

Company to plug at: Hour: A.M. Day: 26 Month: February Year: 93

Plugging proposal received from: Tom Alm

Company: Emphasis Oil Operations Phone: _____

Were: Order 190 sx. 60/40 pozmix - 6% gel. - 3% c.c. Condition
hole with heavy mud. 8 5/8" set @ 319' w/195 sx. Witnessed by Carl
Goodrow. Halliburton Cement Company.

Plugging Proposal Received by: Carl Goodrow
Plugging operations attended by agent? All[], Part[], None[]

Completed: Hour: 2:00A.M., Day: 26, Month: February, Year: 93

Actual plugging report: Spot cement plugs and displaced mud.
1st. plug @ 2360' w/ 25 sx. cement.
2nd. plug @ 1500' w/100 sx. cement with hulls.
3rd. plug @ 370' w/ 40 sx. cement.
4th. plug @ 40' w/ 10 sx. cement with W.P.
Circulate 15 sx. in rathole.

Remarks: Anhy. 2350' - 2378'.

Condition of casing(in hole): GOOD BAD Anhy. plug: YES NO
Bottom plug(in place): YES , CALC , NO Dakota plug: YES NO
Plugged through TUBING , CASING . Elevation: 2740 GL 04-01-1993

I did did not observe the plugging.

Carl Goodrow
CONSERVATION DIVISION
WICHITA, KANSAS

(agent)

Form CP-2/3

RECEIVED
STATE CORPORATION COMMISSION

INVOICED
DATE 4-1-93
INV. NO. 37541