

To: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

API NUMBER 15-179-20,674-00-06

NW, Sec. 13, T 9 S, R 28 W/E

990 feet from N/S section line

990 feet from W/E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5430

Lease Name Ock Well # 1

Operator: Energy Three Inc.  
Name & Address: Box 1505, Great Bend, Pa.  
67530

County Sheardon

Well Total Depth 4152 feet \$134.94

Conductor Pipe: Size \_\_\_\_\_ feet

Surface Casing: Size 8 5/8" feet 291'

Abandoned Oil Well \_\_\_\_\_ Gas Well \_\_\_\_\_ Input Well \_\_\_\_\_ SWD Well \_\_\_\_\_ D&A X

Other well as hereinafter indicated \_\_\_\_\_

Plugging Contractor Big Three Drilling Co. Inc. License Number 374

Address Box 52, Gorham, Pa. 67640

Company to plug at: Hour: 2:45 PM Day: 14 Month: 2 Year: 19 83

VERBAL PLUGGING ORDERS GIVEN TO Tony Langhuffer

(company name) Big Three Drilling Co. Inc. (phone) 913-483-5644

were: Order 190 lbs. 50% pozmix - 6% Gel. 3% Cal. Cl. & 8 5/8" plug.  
Spotted w/ drill stem w/ heavy mud between all plugs. 1st plug C 2380'  
w/ 20 lbs. 2nd plug C 1500' w/ 100 lbs. 3rd plug C 350' w/ 40 lbs.  
4th plug - solid bridge of hulls & plug C 40' w/ 10 lbs.  
Circulate 10 lbs in rat hole & 10 lbs in mouse hole.

Signed G. R. Schell (TECHNICIAN)

Plugging Operations attended by Agent?: All \_\_\_\_\_ Part \_\_\_\_\_ None X

Operations Completed: Hour: 2:45 PM Day: 14 Month: 2 Year: 19 83

ACTUAL PLUGGING REPORT 8 5/8" - 291' sp. cas. w/ 215 lbs. 50% pozmix - 4% Gel. - 3% Cal. Cl.

Ordered 190 lbs. 50% pozmix - 6% Gel. - 3% Cal. Cl. & 8 5/8" plug. Spot w/ drill  
stem w/ heavy mud between all plugs. 1st plug C 2380' w/ 20 lbs.  
2nd plug C 1500' w/ 100 lbs. 3rd plug C 350' w/ 40 lbs. 4th plug - solid  
bridge of hulls & plug C 40' w/ 10 lbs.  
Circulated 10 lbs in rat hole & 10 lbs in mouse hole

Remarks: \_\_\_\_\_

RECEIVED  
STATE CORPORATION COMMISSION

MAR 14 1983  
03-14-1983  
CONSERVATION DIVISION  
Wichita, Kansas

I hereby certify that the above plugging instructions were given as herein stated  
and that I (did/did not) observe this plugging.

INVOICED

DATE 4-4-83  
INV. NO. 3836-W

Signed G. R. Schell (TECHNICIAN)