

To: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

API NUMBER 15-179-20,722-00-03

SW-SW-NE, Sec. 13, T 9 S, R 28 E

2310 feet from N/S section line

2310 feet from W/E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5430

Lease Name OCHS Well # 2

Operator: ENERGY THREE, INC.  
Name & Address: P.O. BOX 1205  
GREAT BEND, KANSAS  
67530

County SHERIDAN

Well Total Depth 4120 feet 134.23

Conductor Pipe: Size 0 feet

Surface Casing: Size 8 5/8 feet 304

Abandoned Oil Well \_\_\_\_\_ Gas Well \_\_\_\_\_ Input Well \_\_\_\_\_ SWD Well \_\_\_\_\_ D&A

Other well as hereinafter indicated \_\_\_\_\_

Plugging Contractor BIG THREE DRILLING INC. License Number 5826 TAG #

Address P.O. BOX 52 GORHAM, MS. 67640

Company to plug at: Hour: 12:00 AM Day: 21st Month: Dec Year: 1983

VERBAL PLUGGING ORDERS GIVEN TO STAN LOVE LADY

(company name) BIG THREE DRILLING (phone) 316-792-5968

were:

8 5/8" - 304 E.S.P. CUC #1200 50% Pozmix 2% 3% GEL - CA-CL. BY ALLIED CONT.  
ORDER 205 50% Pozmix 6% GEL - 3% CA-CL, 1st CELLO FLAKE 8 5/8" PLUG  
SPOT WITH DRILL STEM - TURN HOLE OVER, HEAVY MUD BETWEEN ALL PLUGS.  
H-C. WELL - NO ARBUCKLE, ELEV. 2748' - ANH. 2358'

Signed [Signature] (TECHNICIAN) 201C

Plugging Operations attended by Agent?: All \_\_\_\_\_ Part \_\_\_\_\_ None

Operations Completed: Hour: 12:00 AM Day: 21st Month: Dec Year: 1983

ACTUAL PLUGGING REPORT

ORDERED 205 50% Pozmix 6% GEL, 3% CA-CL, 1st CELLO FLAKE 8 5/8" PLUG  
SPOTTED WITH DRILL STEM, TURNED HOLE OVER, HEAVY MUD BETWEEN ALL PLUGS  
1st Plug @ 2370 FT #125 50% CMT., 2nd Plug @ 1380 FT #100 50% CMT., 1st CELLO FLAKE  
3rd Plug @ 330 FT #150 50% CMT., 4th Plug SOLID BRIDGE HULL'S-PLUG @ 40 FT #10 50% CMT.  
10 50% IN RAT-HOLE (CIR) 10 50% IN MOUSE HOLE (CIR) BY ALLIED CONT.

Remarks: \_\_\_\_\_

I hereby certify that the above plugging instructions were given as herein stated and that I (did / did not) observe this plugging.

INVOICED

RECEIVED STATE CORPORATION COMMISSION

DATE 1-9-84

INV. NO. 8136 W

DEC 27 1983 12-27-1983

CONSERVATION DIVISION Wichita, Kansas

Signed [Signature] (TECHNICIAN) 201C