

KANSAS

Form CP-3  
Rev. 6-4-68

STATE CORPORATION COMMISSION  
CONSERVATION DIVISION AGENT'S REPORT

RECEIVED  
STATE CORPORATION COMMISSION  
MAY 22 1974  
05-22-1974  
CONSERVATION DIVISION  
Wichita, Kansas

J. Lewis Brock  
Administrator  
P. O. Box 17027  
Wichita, Kansas 67217

15-179-20385-00-00

Operator's Full Name Chief Drilling Company, Incorporated & P.S. Petroleum Company,  
Complete Address 905 Century Plaza, Wichita, Kansas.  
Lease Name Fore, etal Well No. 1  
Location CE/2-SE-SE Sec. 35 Twp. 9 Rge. (E) (W) 26  
County Sheridan Total Depth 4080'  
Abandoned Oil Well        Gas Well        Input Well        SWD Well        D & A X  
Other well as hereafter indicated         
Plugging Contractor Chief Drilling Company, Incorporated,  
Address Above License No.         
Operation Completed: Hour 2:00 AM Day 19 Month 5 Year 1974

The above well was plugged as follows:

217'--8 5/8" Surface casing, cement circulated with ---.  
Top of Dakota section @ 1050'.

Circulated hole with heavy mud. Pulled DP to 1275' and displaced 110 Cu. Ft. cement  
thru DP from 1275' to 950'. Pulled DP to 225' and displaced 30 Cu. Ft. cement thru  
DP from 225' to 150'. Pulled DP, set bridge @ 40' with 1/2 sack hulls and 10 Cu. Ft.  
cement to bottom of cellar.

I hereby certify that the above well was plugged as herein stated.

Signed: A. L. Dschels  
Well Plugging Supervisor

INVOICED

DATE 5/23/74  
INV. NO. 9183-W