

KANSAS

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. P. Roberts
Administrator
500 Insurance Building
Wichita, Kansas 67202

RECEIVED
STATE CORPORATION COMMISSION
DEC 15 1967
12-15-1967
CONSERVATION DIVISION
WICHITA, KANSAS

15-179-20064-00-00

Operator's Full Name Leo J. Dreiling and Sons, Incorporated,

Complete Address R. R. #2, Victoria, Kansas. 67671

Lease Name Inloes Well No. 1

Location NW-NW Sec. 36 Twp. 9 Rge. (E) (W) 26

County Sheridan Total Depth 4111'

Abandoned Oil Well Gas Well Input Well SWD Well D & A X

Other well as hereafter indicated

Plugging Contractor Above

Address License No.

Operation Completed: Hour 9:30 AM Day 12 Month 12 Year 1967

The above well was plugged as follows:

209'--8 5/8" Surface pipe, cement circulated with 150 Sx.
Dakota section from 1050' to 1250'.

Circulated hole with heavy mud. Pulled DP to 1275' and displaced 100 Sx. cement thru
DP from 1275' to 955'. Pulled DP to 210' and displaced 20 Sx. cement thru DP from
210' to 150'. Pulled DP, set bridge @ 40' with 1/2 sack hulls and 10 Sx. cement to
bottom of cellar.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: R. L. Schale
Well Plugging Supervisor

DATE 12/15/67
INV. NO. 6917-W