



KANSAS

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. P. Roberts
Administrator
500 Insurance Building
Wichita, Kansas 67202

15-179-20212-00-00

RECEIVED
STATE CORPORATION COMMISSION
JUN 16 1969
CONSERVATION DIVISION
Wichita, Kansas
06-16-1969

Operator's Full Name Petroleum, Incorporated,

Complete Address: 300 West Douglas, Wichita, Kansas.

Lease Name O'Dell Well No. 1

Location SE-NE-SE Sec. 1 Twp. 9 Rge. (E) (W) 27

County Sheridan Total Depth 4004'

Abandoned Oil Well Gas Well Input Well SWD Well D & A X

Other well as hereafter indicated:

Plugging Contractor: Garvey Drilling Company,

Address: Rte. #2, Great Bend, Kansas. License No.

Operation Completed: Hour 11:45AM Day 11 Month 6 Year 1969

The Above well was plugged as follows:

247'--8 5/8" Surface casing, cement circulated with 180 Sx.
Top of Dakota section @ 975'.

Circulated hole with heavy mud. Pulled DP to 1200' and displaced 100 Sx. cement thru
DP from 1200' to 875'. Pulled DP to 275' and displaced 20 Sx. cement thru DP from
275' to 215'. Pulled DP, set bridge @ 40' with 1/2 sack hulls and 10 Sx. cement to
bottom of cellar.

I hereby certify that the above well was plugged as herein stated.

INVOICED
DATE 6/16/69
INV. NO. 9948-W

Signed: W. L. Nichols
Well Plugging Supervisor