

R

Form CP-3
Rev. 6-4-68

KANSAS

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. Lewis Brock
Administrator
P. O. Box 17027
Wichita, Kansas 67217

RECEIVED
STATE CORPORATION COMMISSION
SEP 24 1973
09-24-1973
CONSERVATION DIVISION
Wichita, Kansas

15-179-20366-00-00

Operator's Full Name Chief Drilling Company, Incorporated,

Complete Address 905 Century Plaza, Wichita, Kansas.

Lease Name Popp Well No. 1

Location SW-SW-NE Sec. 1 Twp. 9 Rge. (E) (W) 27

County Sheridan Total Depth 4030'

Abandoned Oil Well Gas Well Input Well SWD Well D & A X

Other well as hereafter indicated

Plugging Contractor Above

Address License No.

Operation Completed: Hour 5:00 PM Day 22 Month 9 Year 1973

The above well was plugged as follows:

222'--8 5/8" Surface casing, cement circulated with 150 Sx.
Top of Dakota section @ 1125'.

Circulated hole with heavy mud. Pulled DP to 1375' and displaced 110 Cu. Ft. cement
thru DP from 1375' to 1050'. Pulled DP to 245' and displaced 30 Cu. Ft. cement thru
DP from 245' to 170'. Pulled DP, set bridge @ 40' with 1/2 sack hulls and 10 Cu. Ft.
cement to bottom of cellar.

INVOICED

I hereby certify that the above well was plugged as herein stated.

DATE 9-24-73

Signed: A. L. Dicks
Well Plugging Supervisor

INV. NO. 7956-4