

KANSAS

*Handwritten mark*

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. P. Roberts  
Administrator  
500 Insurance Building  
Wichita, Kansas 67202

15-179-20099-00-00

RECEIVED  
STATE CORPORATION COMMISSION  
MAY 20 1968  
CONSERVATION DIVISION  
Wichita, Kansas  
05-20-1968

Operator's Full Name Rains & Williamson Oil Company, Incorporated,

Complete Address: 1425 Wichita Plaza, Wichita, Kansas.

Lease Name Shafer Well No. 1

Location CNE-SW, 1980' FSL & 1980' FWL Sec. 2 Twp. 9 Rge. (E) (W) 27

County Sheridan Total Depth 4107

Abandoned Oil Well      Gas Well      Input Well      SWD Well      D & A X

Other well as hereafter indicated:     

Plugging Contractor: Above

Address:      License No.     

Operation Completed: Hour 5:15 AM Day 14 Month 5 Year 1968

The Above well was plugged as follows:

321'--8 5/8" Surface pipe, cement circulated with 175 Sx.  
Top of Dakota section @ 1085'.

Circulated hole with heavy mud. Pulled DP to 1310' and displaced 100 Sx. cement thru  
DP from 1310' to 985'. Pulled DP to 335' and displaced 20 Sx. cement thru DP from  
335' to 275'. Pulled DP, set bridge @ 40' with 1/2 sack hulls and 10 Sx. cement to  
bottom of cellar.

I hereby certify that the above well was plugged as herein stated.

Signed: M. L. Nichols  
Well Plugging Supervisor

INVOICED

DATE 5/20/68  
INV. NO. 7770-4