



STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION

J. Lewis Brock
Administrator
P. O. Box 17027
Wichita, Kansas 67217

15-179-20034-00-02

OCT 21 1974
10-21-1974
CONSERVATION DIVISION
Wichita, Kansas

Operator's Full Name Larry G. Stephenson,

Complete Address 340 Farm Credit Bank Building, Wichita, Kansas.

Lease Name Mosier Well No. H-1

Location NE-SE-NE Sec. 4 Twp. 9 Rge. (E) (W) 27

County Sheridan Total Depth 4006'

Abandoned Oil Well Gas Well Input Well SWD Well D & A

Other well as hereafter indicated _____

Plugging Contractor Pipe Pullers, Incorporated.

Address P. O. Box #486, Ellinwood, Kansas. License No. 462

Operation Completed: Hour 5:30 PM Day 15 Month 10 Year 1974

The above well was plugged as follows:

203'--8 5/8" Surface casing, cement circulated with --?

4001'--5 1/2" Production casing cemented on bottom with 100 Sx. No plug-back indicated.

Top of perforations @ 3672'.

Pushed plug to 3750', sanded well back to 3725' and set 4 Sx. cement with dump bailer.

Pulled 5 1/2" casing (1010') and squeezed well initially with 5 sacks hulls and 8 sacks gel, followed with 110 Cu. Ft. cement from 1325' to 1000' then 19 sacks gel from 1000' to 240' and followed with 30 Cu. Ft. cement from 240' to 165' then 3 sacks gel from 165' to 45' and finally 15 Cu. Ft. cement from 45' to bottom of cellar. (Mudding and cementing by Allied Cementing, Inc.).

I hereby certify that the above well was plugged as herein stated.

Signed: W. L. Nichols
Well Plugging Supervisor

INVOICED

DATE 10/23/74

INV. NO. 152-W