

R

KANSAS

Form CP-3
Rev. 6-9-67

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. P. Roberts
Administrator
500 Insurance Building
Wichita, Kansas 67202

RECEIVED
STATE CORPORATION COMMISSION

NOV 29 1967

11-29-1967

CONSERVATION DIVISION
Wichita, Kansas

15-179-20057-00-00

Operator's Full Name Donald C. Slawson,

Complete Address 408 One-Twenty Building, Wichita, Kansas.

Lease Name Mosier Well No. F-1

Location CN/2-N/2 SE ^{KCC} _{24P} Sec. 4 Twp. 9 Rge. (E) (W) 27

County Sheridan Total Depth 4025'

Abandoned Oil Well Gas Well Input Well SWD Well D & A X

Other well as hereafter indicated

Plugging Contractor Slawson Drilling Company, Incorporated.

Address 408 One-Twenty Bldg., Wichita, Ks. License No.

Operation Completed: Hour 1:00PM Day 19 Month 11 Year 1967

The above well was plugged as follows:

246'--8 5/8" Surface pipe, cement circulated with 185 Sx.
Dakota section from 1090' to 1600'.

Circulated holw with heavy mud. Pulled DP to 1320' and displaced 100 Sx. cement thru
DP from 1320' to 1000'. Pulled DP to 275' and displaced 20 Sx. cement thru DP from
275' to 215'. Pulled DP, set bridge @ 40' with 1/2 sack hulls and 10 Sx. cement to
bottom of cellar.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: M. R. Nichols
Well Plugging Supervisor

DATE 11-29-67

INV. NO. 6792-W