

KANSAS

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. P. Roberts
Administrator
500 Insurance Building
Wichita 2, Kansas

15-179-20119-00-00

Operator's Full Name Donald C. Slawson,

Complete Address: 408 One-Twenty Building, Wichita, Kansas.

Lease Name Mosier Well No. H-2

Location SW-NE-NE Sec. 4 Twp. 9 Rge. (E) (W) 27

County Sheridan Total Depth 3952

Abandoned Oil Well Gas Well Input Well SWD Well D & A X

Other well as hereafter indicated: _____

Plugging Contractor: Slawson Drilling Company, Incorporated,

Address: 408 One-Twenty Building, Wichita, Kans. License No. _____

Operation Completed: Hour 5:30 PM Day 11 Month 8 Year 1968

The Above well was plugged as follows:

220'--8 5/8" Surface casing, cement circulated with 175 Sx.
Dakota section top @ 1060'.

Circulated hole with heavy mud. Pulled DP to 1300' and displaced 100 Sx. cement thru
DP from 1300' to 975'. Pulled DP to 245' and displaced 20 Sx. cement thru DP from
245' to 185'. Pulled DP, set bridge @ 40' with 1/2 sack hulls and 10 Sx. cement to
bottom of cellar.

I hereby certify that the above well is plugged as herein stated.

RECEIVED

AUG 13 1968

CONSERVATION DIVISION
Wichita, Kansas

Signed: _____

Well Plugging Supervisor

INVOICED

DATE 8/13/68

INV. NO. 8265-W

08-13-1968