

KANSAS

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
MAY 7 1970
CONSERVATION DIVISION
Wichita, Kansas

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

15-179-20249-00-00 05-07-1970

Operator's Full Name Donald C. Slawson

Complete Address 408 One-Twenty Building, Wichita, Kansas.

Lease Name Mosier Well No. H-3

Location SE-SE-NE Sec. 4 Twp. 9 Rge. (E) (W) 27

County Sheridan Total Depth 3985

Abandoned Oil Well Gas Well Input Well SWD Well D & A X

Other well as hereafter indicated

Plugging Contractor Slawson Drilling Company, Incorporated,

Address 408 One-Twenty Building, Wichita, Kansas. License No.

Operation Completed: Hour 10:00 PM Day 5 Month 5 Year 1970

The above well was plugged as follows:

225'--8 5/8" Surface casing, cement circulated with 200 Sx.
Top of Dakota section @ 1100'.

Circulated hole with heavy mud. Pulled DP to 1325' and displaced 100 Sx. cement thru
DP from 1325' to 1000'. Pulled DP to 250' and displaced 25 Sx. cement thru DP from
250' to 175'. Pulled DP, set bridge @ 40' with 1/2 sack hulls and 10 Sx. cement to
bottom of cellar.

I hereby certify that the above well was plugged as herein stated.

Signed: W. L. Nichols
Well Plugging Supervisor

INVOICED
DATE 5/7/70
INV. NO. 1857-u