

KANSAS

**STATE CORPORATION COMMISSION**  
**CONSERVATION DIVISION AGENT'S REPORT**

RECEIVED  
STATE CORPORATION COMMISSION  
NOV 1 1971  
CONSERVATION DIVISION  
Wichita, Kansas  
11-01-1971

J. Lewis Brock  
Administrator  
500 Insurance Building  
Wichita, Kansas 67202

15-179-20290-00-00

Operator's Full Name Kaiser-Francis,

Complete Address 4120 East 51st Street, Tulsa, Oklahoma.

Lease Name Kennedy Well No. D-1

Location SW-NE-SW Sec. 5 Twp. 9 Rge. (E) (W) 27

County Sheridan Total Depth 3952'

Abandoned Oil Well  Gas Well  Input Well  SWD Well  D & A  X

Other well as hereafter indicated \_\_\_\_\_

Plugging Contractor Dreiling Oil, Incorporated,

Address R. R. #2, Victoria, Kansas. License No. \_\_\_\_\_

Operation Completed: Hour 2:15 AM Day 26 Month 10 Year 1971

The above well was plugged as follows:

251'--8 5/8" Surface casing, cement circulated with 175 Sx.  
Top of Dakota section @ 1100'.

Circulated hole with heavy mud. Pulled DP to 1325' and displaced 100 Sx. cement thru  
DP from 1325' to 1000'. Pulled DP to 275' and displaced 25 Sx. cement thru DP from  
275' to 200'. Pulled DP, set bridge @ 40' with 1/2 sack hulls and 10 Sx. cement to  
bottom of cellar.

I hereby certify that the above well was plugged as herein stated.

Signed: W. L. Dickole  
Well Plugging Supervisor

INVOICED

DATE 11/2/71  
INV. NO. 4574-U