

KANSAS



STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

RECEIVED
STATE CORPORATION COMMISSION

SEP 15 1970

CONSERVATION DIVISION
Wichita, Kansas

09-15-1970

15-179-20267-00-00

Operator's Full Name Don E. Pratt,

Complete Address Drawer #370, Hays, Kansas.

Lease Name Mickey Well-No. 1

Location NE-NE-NE Sec. 12 Twp. 9 Rge. (E) (W)27

County Sheridan Total Depth 3570'

Abandoned Oil Well Gas Well Input Well SWD Well D & A X

Other well as hereafter indicated

Plugging Contractor L. J. Dreiling & Sons, Incorporated,

Address R. R. #2, Victoria, Kansas. License No.

Operation Completed: Hour 7:00 AM Day 12 Month 9 Year 1970

The above well was plugged as follows:

249'--8 5/8" Surface casing, cement circulated with 175 Sx.
Top of Dakota section @ 1075'.

Circulated hole with heavy mud. Pulled DP to 1300' and displaced 100 Sx. cement thru
DP from 1300' to 975'. Pulled DP to 275' and displaced 25 Sx. cement thru DP from
275' to 200'. Pulled DP, set bridge @ 40' with 1/2 sack hulls and 10 Sx. cement to
bottom of cellar.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: *H. G. Dickel*
Well Plugging Supervisor

DATE 9-15-70

INV. NO. 2539-W