

KANSAS

2 STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

RECEIVED
STATE CORPORATION COMMISSION
JUN 21 1971
CONSERVATION DIVISION
Wichita, Kansas
06-21-1971

15-179-20267-00-01

Operator's Full Name Don E. Pratt;

Complete Address Drawer #370, Hays, Kansas.

Lease Name Mickey Well No. 1

Location ^{NE}
NW-NE-NE Sec. 12 Twp. 9 Rge. (E) (W)27

County Sheridan Total Depth 4068'

Abandoned Oil Well ^{OWWO}
X Gas Well Input Well SWD Well D & A

Other well as hereafter indicated

Plugging Contractor Knight Casing Pulling Company, Incorporated,

Address Box #405, Chase, Kansas. License No. 624

Operation Completed: Hour 3:00 PM Day 17 Month 6 Year 1971

The above well was plugged as follows:

249'--8 5/8" Surface casing, cement circulated.
4065'--4 1/2" Production casing cemented on bottom with 200 Sx. No plug back nor perforations indicated.

Sanded well back to 4040' and set 3 Sx. cement with dump bailer. Pulled 4 1/2" casing and squeezed well initially with 5 sacks hulls and 8 sacks gel and followed with 100 Sx. cement from 1325' to 1000' then 18 sacks gel from 1000' to 275' and followed with 25 Sx. cement from 275' to 200' then 4 sacks gel from 200' to 40' and finally 10 Sx. cement from 40' to bottom of cellar. (Mudding and cementing operations by Allied Cmtg.).

I hereby certify that the above well was plugged as herein stated.

Signed: *W. L. Dickels*
Well Plugging Supervisor

INVOICED

DATE 6/24/71
INV. NO. 3906-W