

KANSAS

Form CP-3
Rev. 6-9-67

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. P. Roberts
Administrator
500 Insurance Building
Wichita, Kansas 67202

15-179-20052-00-00

RECEIVED
STATE CORPORATION COMMISSION
NOV 6 1967
11-06-1967
CONSERVATION DIVISION
Wichita, Kansas

Operator's Full Name Nadel and Gussman,

Complete Address 625 Union Center, Wichita, Kansas.

Lease Name Eberle Well No. 1

Location Approximate CNE-NW Sec. 17 Twp. 9 Rge. (E) (W) 27

County Sheridan Total Depth 4100'

Abandoned Oil Well Gas Well Input Well SWD Well D & A X

Other well as hereafter indicated

Plugging Contractor Muffin Drilling Company.

Address 617 Union Center, Wichita, Kansas. License No.

Operation Completed: Hour 8:00AM Day 28 Month 10 Year 1967

The above well was plugged as follows:

231'--8 5/8" Surface pipe, cement circulated with 175 Sx.
Dakota section from 1200' to 1040'.

Circulated hole with heavy mud. Pulled DP to 1227' and displaced 100 Sx. cement thru
D P from 1227' to 900'. Pulled DP to 240' and displaced 20 Sx. cement thru DP from
240' to 180'. Pulled DP, set bridge @ 40' with 1/2 sack hails and 10 Sx. cement to
bottom of cellar.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: M. L. Dickels
Well Plugging Supervisor

DATE 11/6/67
INV. NO. 6623-W