

KANSAS

*Handwritten mark*

STATE CORPORATION COMMISSION  
CONSERVATION DIVISION AGENT'S REPORT

RECEIVED  
STATE CORPORATION COMMISSION  
AUG 7 1972  
08-07-1972  
CONSERVATION DIVISION  
Wichita, Kansas

J. Lewis Brock  
Administrator  
500 Insurance Building  
Wichita, Kansas 67202

15-179-20318-00-00

Operator's Full Name Chief Drilling Company, Incorporated,  
Complete Address 905 Century Plaza, Wichita, Kansas.  
Lease Name J. Meyers Well No. 1  
Location App:-SE-NW-NW Sec. 18 Twp. 9 Rge. (E) (W) 27  
County Sheridan Total Depth 3387'  
Abandoned Oil Well        Gas Well        Input Well        SWD Well        D & A X  
Other well as hereafter indicated         
Plugging Contractor Above  
Address        License No.         
Operation Completed: Hour 5:00 PM Day 1 Month 8 Year 1972

The above well was plugged as follows:

224'--8 5/8" Surface casing, cement circulated with 170 Sx.  
Top of Dakota section @ 1225'.

Circulated hole with heavy mud. Pulled DP to 1450' and displaced 110 Cu. Ft. cement  
thru DP from 1450' to 1125'. Pulled DP to 240' and displaced 30 Cu. Ft. cement thru  
DP from 240' to 165'. Pulled DP, set bridge @ 40' with 1/2 sack hulls and 10 Cu. Ft.  
cement to botto m of cellar.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: W. L. Nichols  
Well Plugging Supervisor

DATE 8-7-72  
INV. NO. 6121-10