

KANSAS

STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT'S REPORT

J. Lewis Brock
Administrator
P. O. Box 17027
Wichita, Kansas 67217

15-179-20168-00-00

RECEIVED
STATE CORPORATION COMMISSION
MAR 5 1973
CONSERVATION DIVISION
Wichita, Kansas
03-05-1973

Operator's Full Name Drilling Oil, Incorporated.

Complete Address Victoria, Kansas.

Lease Name Ochs Well No. 1

Location SE-SW-SW Sec. 13 Twp. 9 Rge. (E) (W) 28

County Sheridan Total Depth 4185'

Abandoned Oil Well Gas Well Input Well SWD Well D & A

Other well as hereafter indicated _____

Plugging Contractor Russ Casing Pulling, Incorporated,

Address Box #1082, Great Bend, Kansas. License No. 623

Operation Completed: Hour 10:15 AM Day 28 Month 2 Year 1973

The above well was plugged as follows:

280'--8 5/8" Surface casing, cement circulated.
4106'--4 1/2" Production casing, cemented on bottom with 150 Sx. No plug back indicated.
Top of perforations @ 3912'.

Pushed plug to 3875', sanded back from 3875' to 3850' and set 4 Sx. cement with
dump bailer. Pulled 4 1/2" casing (1520') and squeezed well initially with 5 sacks
hulls and 9 sacks gel and followed with 110 Cu. Ft. cement from 1175' to 1150' then
21 sacks gel from 1150' to 300' and followed with 30 Cu. Ft. cement from 300' to
225'. Then 5 sacks gel from 225' to 25' and finally 10 Cu. Ft. cement from 25' to
bottom of cellar. (Mudding and cementing operations by Allied Cementing Co., Inc.).

I hereby certify that the above well was plugged as herein stated.

Signed: W. L. Nichols
Well Plugging Supervisor

INVOICED
DATE 3/5/73
INV. NO. 7096-W