

KANSAS

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED  
STATE CORPORATION COMMISSION  
FEB 19 1969  
CONSERVATION DIVISION  
Wichita, Kansas  
02-19-1969

J. P. Roberts  
Administrator  
500 Insurance Building  
Wichita, Kansas 67202

15-179-20186-00-00

Operator's Full Name Dreiling and Hiko Bell Mining & Oil Company,

Complete Address: R. R. #2, Victoria, Kansas.

Lease Name Ochs Well No. 2

Location SW-NE-SW Sec. 13 Twp. 9 Rge. (E) (W) 28

County Sheridan Total Depth 4150'

Abandoned Oil Well      Gas Well      Input Well      SWD Well      D & A X

Other well as hereafter indicated:     

Plugging Contractor: L. J. Dreiling & Sons, Incorporated,

Address: R. R. #2, Victoria, Kansas. License No.     

Operation Completed: Hour 9:00AM Day 16 Month 2 Year 1969

The Above well was plugged as follows:

255'--8 5/8" Surface casing, cement circulated with 175 Sx.  
Top of Dakota section @ 1225'.

Circulated hole with heavy mud. Pulled DP to 1450' and displaced 100 Sx. cement thru  
DP from 1450' to 1125'. Pulled DP to 275' and displaced 20 Sx. cement thru DP from  
275' to 215'. Pulled DP, set bridge @ 40' with 1/2 sack hulls and 10 Sx. cement to  
bottom of cellar.

I hereby certify that the above well was plugged as herein stated,

INVOICED

Signed: W. D. Nichols  
Well Plugging Supervisor

DATE 2/19/69  
INV. NO. 9357-W