

KANSAS

Form CP-3
Rev. 6-26-62

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. P. Roberts
Administrator
500 Insurance Building
Wichita, Kansas 67202

15-179-20105-00-00

RECEIVED
STATE CORPORATION COMMISSION
JUN 4 1968
CONSERVATION DIVISION
Wichita, Kansas
06-04-1968

Operator's Full Name Allison & Balck and Abercrombie Drilling, Incorporated.

Complete Address: 801 Union Center Building, Wichita, Kansas.

Lease Name Friend Well No. 1

Location NE-NW-SE Sec. 19 Twp. 9 Rge. (E) (W) 26

County Sheridan Total Depth 3840

Abandoned Oil Well Gas Well Input Well SWD Well D & A X

Other well as hereafter indicated:

Plugging Contractor: Abercrombie Drilling, Incorporated.

Address: 801 Union Center Building, Wichita, Kansas. License No.

Operation Completed: Hour 10:30PM Day 1 Month 6 Year 1968

The Above well was plugged as follows:

259'--7 5/8" Surface pipe, cement circulated with 125 Sx. (6 3/4" Hole).
Dakota section top @ 960'.

Circulated hole with heavy mud. Pulled DP to 1175' and displaced 80 Sx. cement thru
DP from 1175' to 850'. Pulled DP to 275' and displaced 15 Sx. cement thru DP from
275' to 215'. Pulled DP, set bridge @ 40' with 1/2 sack hulls and 10 Sx. cement to
bottom of cellar.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: M. L. F. J. J. J.
Well Plugging Supervisor

DATE 6/4/68

INV. NO. 97872-4