

KANSAS

Form CP-3  
Rev. 6-9-67

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. P. Roberts  
Administrator  
500 Insurance Building  
Wichita, Kansas 67202

RECEIVED  
STATE CORPORATION COMMISSION  
NOV 13 1967  
11-13-1967  
CONSERVATION DIVISION  
Wichita, Kansas

15-179-20056-00-00

Operator's Full Name Thunderbird Drilling, Incorporated,

Complete Address 400 North Woodlawn, Suite #7, Wichita, Kansas.

Lease Name Chestnut Well No. 1

Location Appr. NE-NE-SW Sec. 22 Twp. 9 Rge. (E) (W)26

County Sheridan Total Depth 4157'

Abandoned Oil Well      Gas Well      Input Well      SWD Well      D & A X

Other well as hereafter indicated     

Plugging Contractor Sage Drilling Company, Incorporated,

Address 500 Bitting Building, Wichita, Ks. License No.     

Operation Completed: Hour 3:15PM Day 9 Month 11 Year 1967

The above well was plugged as follows:

247'--8 5/8" Surface pipe, cement circulated with 165 Sx.  
Dakota section from 1130' to 1305'.

Circulated hole with heavy mud. Pulled DP to 1330' and displaced 100 Sx. cement thru  
DP from 1330' to 1010'. Pulled DP to 270' and displaced 20 Sx. cement thru DP from  
270' to 210'. Pulled DP, set bridge @ 40' with 1/2 sack hulls and 10 Sx. cement to  
bottom of cellar.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: W. L. Nichols  
Well Plugging Supervisor

DATE 11/14/67  
INV. NO. 6683-W