

STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION
AUG 16 1973
08-16-1973
CONSERVATION DIVISION
Wichita, Kansas

J. Lewis Brock
Administrator
P. O. Box 17027
Wichita, Kansas 67217

15-179-20360-00-00

Operator's Full Name Chief Drilling Company, Incorporated & Bill J. Porter,

Complete Address 905 Century Plaza, Wichita, Kansas.

Lease Name Fore Well No. 1

Location CNE-SE Sec. 25 Twp. 9 Rge. (E) (W) 26

County Sheridan Total Depth 4115'

Abandoned Oil Well Gas Well Input Well SWD Well D & A X

Other well as hereafter indicated

Plugging Contractor Chief Drilling Company, Incorporated,

Address 905 Century Plaza, Wichita, Ks. License No.

Operation Completed: Hour 5:30 PM Day 14 Month 8 Year 1973

The above well was plugged as follows:

225'--8 5/8" Surface casing, cement circulated with 150 Sx.
Top of Dakota section @ 900'.

Circulated hole with heavy mud. Pulled DP to 1125' and displaced 110 Cu. Ft. cement
thru DP from 1125' to 800'. Pulled DP to 245' and displaced 30 Cu. Ft. cement thru
DP from 245' to 170'. Pulled DP, set bridge @ 170' with 1/2 sack hulls and 10 Cu. Ft.
cement to bottom of cellar.

I hereby certify that the above well was plugged as herein stated.

Signed: M. L. D. Nichols
Well Plugging Supervisor

INVOICED

DATE 8-16-73

INV. NO. 7785-W