

KANSAS

STATE CORPORATION COMMISSION  
CONSERVATION DIVISION AGENT'S REPORT

RECEIVED  
CORPORATION COMMISSION

NOV 6 1967

11-06-1967

CONSERVATION DIVISION  
Wichita, Kansas

15-179-20054-00-00

J. P. Roberts  
Administrator  
500 Insurance Building  
Wichita, Kansas 67202

Operator's Full Name Thunderbird Drilling, Incorporated,  
Complete Address 400 North Woodlawn, Suite #7, Wichita, Kansas.  
Lease Name Breeden Well No. 1  
Location App: NE-NE-SW Sec. 28 Twp. 9 Rge. (E) (W) 26  
County Sheridan Total Depth 4125'  
Abandoned Oil Well        Gas Well        Input Well        SWD Well        D & A X  
Other well as hereafter indicated         
Plugging Contractor Sage Drilling Company, Incorporated,  
Address 500 Bitting Building, Wichita, Kansas. License No.         
Operation Completed: Hour 4:30AM Day 2 Month 11 Year 1967

The above well was plugged as follows:

247'--8 5/8" Surface pipe, cement circulated with 150 Sx.  
Dakota section from 1275' to 1100'.

Circulated hole with heavy mud. Pulled DP to 1300' and displaced 100 Sx. cement thru  
from 1300' to 980'. Pulled DP to 240' and displaced 25 Sx. cement thru DP from 240'  
to 165'. Pulled DP, set bridge @ 40' with 1/2 sackhulls and 10 Sx. cement to bottom of  
cellar.

I hereby certify that the above well was plugged as herein stated.

Signed: [Signature]  
Well Plugging Supervisor

INVOICED

DATE 11/6/67  
INV. NO. 6627-W