

KANSAS

*2*

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED  
STATE CORPORATION COMMISSION  
OCT 20 1970  
CONSERVATION DIVISION  
Wichita, Kansas  
10-20-1970

J. Lewis Brock  
Administrator  
500 Insurance Building  
Wichita, Kansas 67202

15-179-20272-00-00

Operator's Full Name Dunne-Gardner Petroleum, Incorporated,

Complete Address 200 West Douglas, Wichita, Kansas.

Lease Name Friend Well No. 1

Location NE-NE-SW Sec. 29 Twp. 9 Rge. (E) (W) 26

County Sheridan Total Depth 4025'

Abandoned Oil Well      Gas Well      Input Well      SWD Well      D & A X

Other well as hereafter indicated     

Plugging Contractor Chief Drilling Company, Incorporated,

Address Box #486, Great Bend, Kansas. License No.     

Operation Completed: Hour 10:30 PM Day 18 Month 10 Year 1970

The above well was plugged as follows:

266'--8 5/8" Surface casing, cement circulated with 200 Sx.  
Top of Dakota section @ 1000'.

Circulated hole with heavy mud. Pulled DP to 1240' and displaced 100 Sx. cement thru  
DP from 1240' to 915'. Pulled DP to 275' and displaced 25 Sx. cement thru DP from  
275' to 200'. Pulled DP, set bridge @ 40' with 1/2 sack hulls and 10 Sx. cement to  
bottom of cellar.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: W. S. Nichols  
Well Plugging Supervisor

DATE 10-20-70  
INV. NO. 2722-4