

KANSAS

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION
FEB 7 1969
CONSERVATION DIVISION
Wichita, Kansas
02-07-1969

J. P. Roberts
Administrator
500 Insurance Building
Wichita, Kansas 67202

15-179-2978-00-00

Operator's Full Name Kaiser-Francis,

Complete Address: 909 Palace Building, Tulsa, Oklahoma,

Lease Name B. White Well No. B-1

Location NE-NE-SE Sec. 26 Twp. 9 Rge. (E) (W) 27

County Sheridan Total Depth 4101'

Abandoned Oil Well Gas Well Input Well SWD Well D & A X

Other well as hereafter indicated:

Plugging Contractor: L. J. Dreiling & Sons, Incorporated,

Address: R. R. #2, Victoria, Kansas. License No.

Operation Completed: Hour 6:00AM Day 5 Month 2 Year 1969

The Above well was plugged as follows:

271'--8 5/8" Surface casing, cement circulated with 175 Sx.
Top of Dakota section @ 1125'.

Circulated hole with heavy mud. Pulled DP to 1345' and displaced 100 Sx. cement thru
DP from 1345' to 1120'. Pulled DP to 275' and displaced 20 Sx. cement thru DP from
275' to 215'. Pulled DP, set bridge @ 40' with 1/2 sack hulls and 10 Sx. cement to
bottom of cellar.

I hereby certify that the above well was plugged as herein stated.

Signed: N. L. Nichols
Well Plugging Supervisor

INVOICED

DATE 2/7/69
INV. NO. 9298-11