

KANSAS

Form CP-3
Rev. 6-26-62

R

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. P. Roberts
Administrator
500 Insurance Building
Wichita, Kansas 67202

RECEIVED
STATE CORPORATION COMMISSION
JUL 15 1968
CONSERVATION DIVISION
Wichita, Kansas

15-179-2011-00-00

07-15-1968

Operator's Full Name Donald C. Slawson,

Complete Address: 408 One-Twenty Building, Wichita, Kansas.

Lease Name Gallagher Well No. A-1

Location CSE-NW Sec. 32 Twp. 9 Rge. (E) (W) 27

County Sheridan Total Depth 4115'

Abandoned Oil Well Gas Well Input Well SWD Well D & A X

Other well as hereafter indicated: _____

Plugging Contractor: Slawson Drilling Company, Incorporated,

Address: 408 One-Twenty Building, Wichita, Kans. License No. _____

Operation Completed: Hour 3:00 PM Day 8 Month 7 Year 1968

The Above well was plugged as follows:

253'--8 5/8" Surface pipe, cement circulated with 190 Sx.
Top of Dakota section @ 1135'.

Circulated hole with heavy mud. Pulled DP to 1360' and displaced 100 Sx. cement thru
DP from 1360' to 1035'. Pulled DP to 275' and displaced 20 Sx. cement thru DP from
275' to 215'. Pulled DP, set bridge @ 40' with 1/2 sack hulls and 10 Sx. cement to
bottom of cellar.

I hereby certify that the above well was plugged as herein stated.

Signed: W. A. Nichols
Well Plugging Supervisor

INVOICED

DATE 7-15-68

INV. NO. 8121-w