

KANSAS

2
STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. Lewis Brock
Administrator
P. O. Box 17027
Wichita, Kansas 67217

15-179-20336-00-00

RECEIVED
STATE CORPORATION COMMISSION
DEC 8 - 1972
12-08-1972
CONSERVATION DIVISION
Wichita, Kansas

Operator's Full Name Pate-Dombaugh and Martin Exploration,
Complete Address 502 Union Center, Wichita, Kansas.
Lease Name Berens Well No. 1
Location NE-NW-NW Sec. 33 Twp. 9 Rge. (E) (W) 27
County Sheridan Total Depth 4100'
Abandoned Oil Well Gas Well Input Well SWD Well D & A X
Other well as hereafter indicated
Plugging Contractor Abercrombie Drilling, Incorporated,
Address 801 Union Center, Wichita, Kansas License No.
Operation Completed: Hour 3:00 AM Day 7 Month 12 Year 1972

The above well was plugged as follows:

Circulated hole with heavy mud. Pulled DP to 1275' and displaced 110 Cu. Ft. cement
thru DP from 1275' to 950'. Pulled DP to 245' and displaced 30 Cu. Ft. cement thru
DP from 245' to 170'. Pulled DP, set bridge @ 40' with 1/2 sack hulls and 10 Cu. Ft.
cement to bottom of cellar.

I hereby certify that the above well was plugged as herein stated.

Signed: *W. S. Nichols*
Well Plugging Supervisor

INVOICED

DATE 12/8/72

INV. NO. 6712-W