

KANSAS

STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT'S REPORT

J. Lewis Brock
Administrator
P. O. Box 17027
Wichita, Kansas 67217

15-179-20383-00-00

RECEIVED
STATE CORPORATION COMMISSION
MAY 3 - 1974
05-03-1974
CONSERVATION DIVISION
Wichita, Kansas

Operator's Full Name Chief Drilling Company, Incorporated,
Complete Address 905 Century Plaza, Wichita, Kansas.
Lease Name Ochs Well No. 1
Location SE-NW Sec. 1 Twp. 9 Rge. (E) (W) 28
County Sheridan Total Depth 2490'
Abandoned Oil Well Gas Well Input Well SWD Well D & A X
Other well as hereafter indicated
Plugging Contractor Above
Address License No.

Operation Completed: Hour 7:30 PM Day 29 Month 4 Year 1974

The above well was plugged as follows:

254'--8 5/8" Surface casing, cement circulated.
Top of Dakota section @ 1100'.

Circulated hole with heavy mud. Pulled DP to 1325' and displaced 110 Cu. Ft. cement
thru DP from 1325' to 1000'. Pulled DP to 275' and displaced 30 Cu. Ft. cement thru
DP from 275' to 200'. Pulled DP, set bridge @ 40' with 1/2 sack hulls and 10 Cu. Ft.
cement to bottom of cellar.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: M. L. D. Jickels
Well Plugging Supervisor

DATE 5/18/74
INV. NO. 9056-W