

KANSAS

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. P. Roberts  
Administrator  
500 Insurance Building  
Wichita, Kansas 67202

RECEIVED  
STATE CORPORATION COMMISSION  
FEB 17 1969  
CONSERVATION DIVISION  
Wichita, Kansas  
02-17-1969

15-179-20182-00-00

Operator's Full Name Kaiser-Francis,

Complete Address: 909 Palace Building, Tulsa, Oklahoma.

Lease Name Farber Well No. B-1

Location CSE-SE Sec. 3 Twp. 9 Rge. (E) (W) 28

County Sheridan Total Depth 4175'

Abandoned Oil Well      Gas Well      Input Well      SWD Well      D & A X

Other well as hereafter indicated:     

Plugging Contractor: L. J. Dreiling & Sons, Incorporated,

Address: R. R. #2, Victoria, Kansas. License No.     

Operation Completed: Hour 2:30PM Day 11 Month 2 Year 1969

The Above well was plugged as follows:

257'--8 5/8" Surface casing, cement circulated with 175 Sx.  
Top of Dakota Section @ 1200'.

Circulated hole with heavy mud. Pulled DP to 1135' and displaced 100 Sx. cement thru  
DP from 1135' to 1110'. Pulled DP to 275' and displaced 20 Sx. cement thru DP from  
275' to 215'. Pulled DP, set bridge @ 40' with 1/2 sack hulls and 10 Sx. cement to  
bottom of cellar.

I hereby certify that the above well was plugged as herein stated.

Signed: W. L. Nichols  
Well Plugging Supervisor

INVOICED

DATE 2/17/69  
INV. NO. 9338-W