

KANSAS
STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. P. Roberts
Administrator
500 Insurance Building
212 North Market
Wichita 2, Kansas

RECEIVED
STATE CORPORATION COMMISSION
APR 1 1968
CONSERVATION DIVISION
Wichita, Kansas
04-11-1968

15-179-20082-00-00

Operator's Full Name Graves Drilling Company,

Complete Address: 505 Union Center, Wichita, Kansas.

Lease Name Pratt Well No. 1

Location SE-SE-SE Sec. 4 Twp. 9 Rge. (E) (W) 28

County Sheridan Total Depth 4135

Abandoned Oil Well Gas Well Input Well SWD Well D & A X

Other well as hereafter indicated: _____

Plugging Contractor: Murfin Drilling Company,

Address: 617 Union Center, Wichita, Kansas. License No. _____

Operation Completed: Hour 7:00 PM Day 27 Month 3 Year 1968

The Above well was plugged as follows:

242'--8 5/8" Surface pipe, cement circulated with 180 Sx.
Top of Dakota section @ 1150'.

Circulated hole with heavy mud. Pulled DP to 1450' and displaced 100 Sx. cement thru
DP from 1450' to 1125'. Pulled DP to 270' and displaced 20 Sx. cement thru DP from
270' to 210'. Pulled DP, set bridge @ 40' with 1/2 sack hulls and 10 Sx. cement to
bottom of cellar.

I hereby certify that the above well was plugged as herein stated.

INVOICED

DATE 4/1/68

INV. NO. 7500-11

Signed: N. L. Dickels
Well Plugging Supervisor