

KANSAS

Form CP-3
Rev. 6-4-68

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION

J. Lewis Brock
Administrator
P. O. Box 17027
Wichita, Kansas 67217

15-179-20364-00-00

SEP 17 1973
09-17-1973
CONSERVATION DIVISION
Wichita, Kansas

Operator's Full Name Geo. A. Reed

Complete Address 1223 Union Nat'l Bldg., Wichita, Kansas

Lease Name Farber Well No. 1

Location SW NW NE Sec. 4 Twp. 9 Rge. (E) (W)28

County Sheridan Total Depth 4055'

Abandoned Oil Well Gas Well Input Well SWD Well D & A XX

Other well as hereafter indicated _____

Plugging Contractor Abercrombie Drlg.

Address Wichita, Kansas License No. _____

Operation Completed: Hour 12:30 P Day 15 Month 9 Year 1973

The above well was plugged as follows:

RTD 4055' 8 5/8 csg set at 253' cwc: 160 sk. Cmt. Mat. 50-50 poz W/6% total gel.
Gunned pits, circulated heavy mud, set cementing plug at 1250' and displaced 70 sk
cmt thru drill pipe. Heavy mud to 240' set cementing plug and displaced 20 sk cmt
thru drill pipe. Heavy mud to 40' set cementing plug, 1/2 sk hulls and 10 sk cmt to
base of cellar.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: Leo P. Messing
Well Plugging Supervisor

DATE 9-17-73

INV. NO. 7913-W