

KANSAS

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. P. Roberts
Administrator
500 Insurance Building
Wichita, Kansas 67202

RECEIVED
STATE CORPORATION COMMISSION
SEP 23 1968
CONSERVATION DIVISION
Wichita, Kansas

15-179-20137-00-00

09-23-1968

Operator's Full Name Imperial Oil Company,

Complete Address: 780 Fourth National Bank Building, Wichita, Kansas.

Lease Name Mosier Well No. B-1

Location CNE-NW Sec. 8 Twp. 9 Rge. (E) (W) 28

County Sheridan Total Depth 4091

Abandoned Oil Well Gas Well Input Well SWD Well D & A X

Other well as hereafter indicated:

Plugging Contractor: Above

Address: License No.

Operation Completed: Hour 6:00 PM Day 21 Month 9 Year 1968

The Above well was plugged as follows:

209'--8 5/8" Surface casing, cement circulated with 185 Sx.
Top of Dakota section @ 1200'.

Circulated hole with heavy mud. Pulled DP to 1425' and displaced 100 Sx. cement thru
DP from 1425' to 1100'. Pulled DP to 215' and displaced 20 Sx. cement thru DP from
215' to 155'. Pulled DP, set bridge @ 40' with 1/2 sack hulls and 10 Sx. cement to
bottom of cellar.

I hereby certify that the above well was plugged as herein stated.

INVOICED

DATE 9/23/68

INV. NO. 8501-W

Signed: [Signature]
Well Plugging Supervisor