

KANSAS



STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION
MAY 27 1968
CONSERVATION DIVISION
Wichita, Kansas
05-27-1968

J. P. Roberts
Administrator
500 Insurance Building
Wichita, Kansas 67202

15-179-20103-00-00

Operator's Full Name Imperial Oil Company,

Complete Address: 780 Fourth National Bank Building, Wichita, Kansas.

Lease Name Pratt Well No. 1

Location CSW-SW Sec. 9 Twp. 9 Rge. (E) (W) 28

County Sheridan Total Depth 4110

Abandoned Oil Well Gas Well Input Well SWD Well D & A X

Other well as hereafter indicated:

Plugging Contractor: Above

Address: License No.

Operation Completed: Hour 10:30PM Day 24 Month 5 Year 1968

The Above well was plugged as follows:

209'--8 5/8" Surface pipe, cement circulated with 185 Sx.

Circulated hole with heavy mud. Pulled DP to 2175' and displaced 100 Sx. cement thru

DP from 2175' to 1850'. Pulled DP to 200' and displaced 25 Sx. cement thru DP from

200' to 120 Sx. Pulled DP, set bridge @ 40' with 1/2 sack hulls and 10 Sx. cement to

bottom of cellar.

I hereby certify that the above well was plugged as herein stated.

Signed: A. S. Nichols
Well Plugging Supervisor

INVOICED
DATE 5/27/68
INV. NO. 7820-U