

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. Lewis Brock  
Administrator  
P. O. Box 17027  
Wichita, Kansas 67217

RECEIVED  
STATE CORPORATION COMMISSION  
DEC 27 1972  
12-27-1972  
CONSERVATION DIVISION  
Wichita, Kansas

15-179-20340-00-00

Operator's Full Name Petroleum Reserves,  
Complete Address Oklahoma City, Oklahoma.  
Lease Name Billinger Well No. 1  
Location CNW-SE Sec. 9 Twp. 9 Rge. (E) (W) 28  
County Sheridan Total Depth 4100'  
Abandoned Oil Well        Gas Well        Input Well        SWD Well        D & A X  
Other well as hereafter indicated         
Plugging Contractor Dreiling Oil, Incorporated,  
Address R. R. #2, Victoria, Kansas. License No.         
Operation Completed: Hour 10:30 PM Day 20 Month 12 Year 1972

The above well was plugged as follows:

210'--8 5/8" Surface casing, cement circulated with 200 Sx.  
Top of Dakota section @ 1175'.

Circulated hole with heavy mud. Pulled DP to 1400' and displaced 110 Cu. Ft. cement  
thru DP from 1400' to 1075'. Pulled DP to 215' and displaced 30 Cu. Ft. cement thru  
DP from 215' to 140'. Pulled DP, set bridge @ 40' with 1/2 sack hulls and 10 Cu. Ft.  
cement to bottom of cellar.

I hereby certify that the above well was plugged as herein stated.

Signed: *H. L. Nichols*  
Well Plugging Supervisor

INVOICED

DATE 12/27/72  
INV. NO. 6791-W