

KANSAS

Form CP-3  
Rev. 6-26-62

*R*

STATE CORPORATION COMMISSION  
CONSERVATION DIVISION AGENT'S REPORT

RECEIVED  
STATE CORPORATION COMMISSION  
DEC 24 1968  
CONSERVATION DIVISION  
Wichita, Kansas  
12-24-1968

J. P. Roberts  
Administrator  
500 Insurance Building  
Wichita, Kansas 67202

15-179-20170-00-00

Operator's Full Name Abercrombie Drilling, Incorporated,

Complete Address: 801 Union Center Building, Wichita, Kansas.

Lease Name Meier Well No. 1

Location SE-NW-SE Sec. 1 Twp. 9 Rge. (E) (W) 30

County Sheridan Total Depth 4250'

Abandoned Oil Well      Gas Well      Input Well      SWD Well      D & A X

Other well as hereafter indicated:     

Plugging Contractor: Above

Address:      License No.     

Operation Completed: Hour 6:00 AM Day 20 Month 12 Year 1968

The Above well was plugged as follows:

318'--7" OD Surface casing, cement circulated with 115 Sx. (6 1/2" Hole).  
Top of Dakota section @ 1375'.

Circulated hole with heavy mud. Pulled DP to 1600' and displaced 60 Sx. cement thru  
DP from 1600' to 1300'. Pulled DP to 335' and displaced 15 Sx. cement thru DP from  
335' to 260'. Pulled DP, set bridge @ 40' with 1/2 sack hulls and 10 Sx. cement to  
bottom of cellar.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: *M. L. Diehls*  
Well Plugging Supervisor

DATE 12-24-68

INV. NO. 9090-W