

KANSAS

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. P. Roberts
Administrator
500 Insurance Building
Wichita, Kansas 67202

RECEIVED
STATE CORPORATION COMMISSION
DEC 16 1968
CONSERVATION DIVISION
Wichita, Kansas

12-16-1968

15-179 20167-00-00

Operator's Full Name Abercrombie Drilling, Incorporated,

Complete Address: 801 Union Center Building, Wichita, Kansas.

Lease Name Calverley Well No. 1

Location CNW-NE Sec. 2 Twp. 9 Rge. (E) (W) 30

County Sheridan Total Depth 4285'

Abandoned Oil Well Gas Well Input Well SWD Well D & A X

Other well as hereafter indicated:

Plugging Contractor: Above

Address: License No.

Operation Completed: Hour 8:00 AM Day 11 Month 12 Year 1968

The Above well was plugged as follows:

329'--7" OD Surface casing, cement circulated with 100 Sx.
Top of Dakota section @ 1425'.

Circulated hole with heavy mud. Pulled DP to 1650' and displaced 60 Sx. cement thru
DP from 1650' to 1325'. Pulled DP to 360' and displaced 15 Sx. cement thru DP from
360' to 300'. Pulled DP, set bridge @ 40' with 1/2 sack hulls and 10 Sx. cement to
bottom of cellar.

I hereby certify that the above well was plugged as herein stated.

Signed: W. D. Richards
Well Plugging Supervisor

INVOICED
DATE 12/17/68
INV. NO. 9045-W