

KANSAS

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. P. Roberts
Administrator
500 Insurance Building
Wichita, Kansas 67202

15-179-20163-00-00

RECEIVED
STATE CORPORATION COMMISSION
DEC 11 1968
CONSERVATION DIVISION
Wichita, Kansas
12-11-1968

Operator's Full Name Norman D. Fitzgerald,

Complete Address: Box #5046, Abilene, Texas.

Lease Name R. R. Morgan Well No. 1

Location SW-NE Sec. 8 Twp. 9 Rge. (E) (W) 30

County Sheridan Total Depth 4311

Abandoned Oil Well Gas Well Input Well SWD Well D & A X

Other well as hereafter indicated:

Plugging Contractor: Red Tiger Drilling Company,

Address: 1720 Wichita Plaza Building, Wichita, Ks. License No.

Operation Completed: Hour 11:00AM Day 8 Month 12 Year 1968

The Above well was plugged as follows:

232'--8 5/8" Surface casing, cement circulated with 200 Sx.
Top of Dakota section @ 1300'.

Circulated hole with heavy mud. Pulled DP to 1525' and displaced 100 Sx. cement thru
DP from 1525' to 1200'. Pulled DP to 245' and displaced 20 Sx. cement thru DP from
245' to 185'. Pulled DP, set bridge @ 40' with 1/2 sack hulls and 10 Sx. cement to
bottom of cellar.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: W. L. Nichols
Well Plugging Supervisor

DATE 12/11/68
INV. NO. 8998-W