

KANSAS

10
STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

15-179-20251-00-00

RECEIVED
STATE CORPORATION COMMISSION
MAY 27 1970
CONSERVATION DIVISION
Wichita, Kansas
05-27-1970

Operator's Full Name Shields Oil Producers, Incorporated,

Complete Address Shields Building, Russell, Kansas.

Lease Name Schiltz Well No. 1-A

Location NW SW-NE Sec. 9 Twp. 9 Rge. (E) (W) 30

County Sheridan Total Depth 4280'

Abandoned Oil Well Gas Well Input Well SWD Well D & A X

Other well as hereafter indicated

Plugging Contractor D. J. Dreiling & Sons, Incorporated,

Address R. R. #2, Victoria, Kansas. License No.

Operation Completed: Hour 11:30 PM Day 23 Month 5 Year 1970

The above well was plugged as follows:

294'--8 5/8" Surface casing, cement circulated with 210 Sx.
Top of Dakota section @ 1350'.

Circulated hole with heavy mud. Pulled DP to 1575' and displaced 100 Sx. cement thru
DP from 1575' to 1250'. Pulled DP to 310' and displaced 25 Sx. cement thru DP from
310' to 235'. Pulled DP, set bridge @ 40' with 1/2 sack hulls and 10 Sx. cement to
bottom of cellar.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: M. L. Nichols
Well Plugging Supervisor

DATE 5/28/70

INV. NO. 1956-W