

State of Kansas



State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)
 P. O. Box 17027 3830 S. Meridian
 WICHITA, KANSAS 67217

VERBAL PERMIT FORM
 (To Be Filed By Plugging Agent)

RECEIVED
 STATE CORPORATION COMMISSION
 MAY 22 1974
 05-22-1974
 CONSERVATION DIVISION
 Wichita, Kansas

J. Lewis Brock
 Administrator
 500 Insurance Building
 Wichita, Kansas 67202

15-179-20385-00-00

Dear Sir:

Mr. Marion Burris of Chief Drlg. Co., Inc., has this date requested permission to plug the following described well:

Mr. Burris guarantees payment of the plugging fee.

Operator's full Name: Chief Drilling Company, Inc., & P S Petroleum Company,

Complete Address: 905 Century Plaza, Wichita, Kansas.

Lease Name: Fore, Etal Well No. 1

Location: CE/2-SE-SE Sec. 35 Twp. 9 Rge. (E)(W) 26

County: Sheridan Total Depth 4080' Oil Well

Gas Well Input Well SWD Well D & A X Lost Hole

Mr. Burris was instructed to plug the well as follows:

217'--8 5/8" Surface casing, cement circulated.
Top of Dakota section @ 1050'.

Circulate hole with heavy mud. Pull DP to 1275' and displace 110 Cu. Ft. cement thru DP. Pull DP to 225' and displace 30 Cu. Ft. cement thru DP. Pull DP, set bridge @ 40' with 1/2 sack hulls and 10 Cu. Ft. cement to bottom of cellar.

Very truly yours,

H. L. Dickel
 Conservation Division Agent