



ROBERT B. DOCKING Governor
WILLIAM L. MITCHELL Chairman
JAMES O. GREENLEAF Commissioner
DALE E. SAFFELS Commissioner
RAYMOND B. HARVEY Secretary
E. EDWARD JOHNSON Gen. Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)
500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS 67202

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

RECEIVED
STATE CORPORATION COMMISSION
MAY 20 1968
CONSERVATION DIVISION
Wichita, Kansas
05-20-1968

J. P. Roberts
Administrator
500 Insurance Building
Wichita, Kansas 67202

15-179-20099-00-00

Dear Sir:

Mr. Bill Walker of Rains & Williamson Oil Co. has this date requested permission to plug the following described well:

Mr. Walker guarantees payment of the plugging fee.

Operator's full Name: Rains & Williamson Oil Company, Incorporated,

Complete Address: 1125 Wichita Plaza Building, Wichita, Kansas.

Lease Name: Shafer Well No. 1
1980' FSL and 1980' FWL

Location: CNE-SW Sec. 2 Twp. 9 Rge. (E)(W) 27

County: Sheridan Total Depth 4107 Oil Well

Gas Well Input Well SWD Well D & A X Lost Hole

Mr. Walker was instructed to plug the well as follows:

321'--8 5/8 Surface casing, cement circulated with 175 Sx.
Top of Dakota section @ 1085'.

Circulate hole with heavy mud. Pull DP to 1310' and displace 100 Sx.
cement thru DP. Pull DP to 335' and displace 20 Sx. cement thru DP.
Pull DP. set bridge @ 40' and 10 Sx. cement to bottom of cellar.

Very truly yours,

W. B. Nichols
Conservation Division Agent