

State of Kansas



State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

P. O. Box 17027 3530 S. Meridian
WICHITA, KANSAS 67217

RECEIVED
STATE CORPORATION COMMISSION

OCT 21 1974
10-21-1974
CONSERVATION DIVISION
Wichita, Kansas

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

15-179-20034-00-02

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

Dear Sir:

Mr. John Glenn of Pipe Pullers, Incorporated has this date requested permission to plug the following described well:

Mr. Glenn guarantees payment of the plugging fee.

Operator's full Name: Larry G. Stephenson,

Complete Address: 340 Farm Credit Bank Building, Wichita, Kansas.

Lease Name: Mosier Well No. H-1

Location: NE-SE-NE Sec. 4 Twp. 9 Rge. (E)(W) 27

County: Sheridan Total Depth 4006' Oil Well x

Gas Well Input Well SWD Well D & A Lost Hole

Mr. Glenn was instructed to plug the well as follows:

203'--8 5/8" Surface casing, cement circulated with --
4001'--5 1/2" Production casing cemented on bottom with 100 Sx. No plug-
back indicated. Top of perforations @ 3672'.

Push plug to 3750', sand back to 3725' and set 4 Sx. cement with dump
bailer. Pull 5 1/2" casing and squeeze well with 5 sacks hulls, 30 sacks
gel and 150 Cu. Ft. cement, staged.

Very truly yours,

R. L. Nichols
Conservation Division Agent