

State of Kansas



WM. H. AVERY Governor
WILLIAM I. MITCHELL Chairman
JAMES O. GREENLEAF Commissioner
HARRY G. WILES Commissioner
RAYMOND B. HARVEY Secretary
E. EDWARD JOHNSON Gen. Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)
500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS 67202

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

RECEIVED
STATE CORPORATION COMMISSION

NOV 29 1967

12-29-1967

J. P. Roberts
Administrator
500 Insurance Building
Wichita 2, Kansas

15-179-20057-00-00 CONSERVATION DIVISION
Wichita, Kansas

Dear Sir:

Mr. Bill Rowe of Slawson Drilling Co. Inc., has this date requested permission to plug the following described well:

Mr. Rowe guarantees payment of the plugging fee.

Operator's full Name: Donald C. Slawson,

Complete Address: 408 One-Twenty Building, Wichita, Kansas.

Lease Name: Mosier Well No. F-1

Location: CN/2-N/2 SE ^{KC} Sec. 4 Twp. 9 Rge. (E)(W) 27

County Sheridan Total Depth 4025 Oil Well

Gas Well Input Well SWD Well D & A X Lost Hole

Mr. Rowe was instructed to plug the well as follows:

246'--8 5/8" Surface pipe, cement circulated with 185 Sx.
Dakota section from 1090' to 1600'.

Circulate hole with heavy mud. Pull DP to 1320' and displace 100 Sx.
cement thru DP. Pull DP to 275' and displace 20 Sx. cement thru DP.
Pull DP, set bridge @ 40' with 1/2 sack hulls and 10 Sx. cement to bottom
of cellar.

Very truly yours,

Conservation Division Agent