



ROBERT B. DOCKING Governor  
DALE E. SAFFELS Chairman  
JULES V. DOTY Commissioner  
JAMES O. GREENLEAF Commissioner  
RAYMOND B. HARVEY Secretary  
JACK GLAVES Gen. Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)  
500 Insurance Bldg. 212 N. Market  
WICHITA, KANSAS 67202

VERBAL PERMIT FORM  
(To Be Filed By Plugging Agent)

J.-P. Roberts  
Administrator  
500 Insurance Building  
Wichita, Kansas 67202

15-179-20119-00-00

Dear Sir:

Mr. Bill Rowe of Slawson Drilling Co. Inc., has this date requested permission to plug the following described well:

Mr. Rowe guarantees payment of the plugging fee.

Operator's full Name: Donald C. Slawson,

Complete Address: 408 One-Twenty Building, Wichita, Kansas.

Lease Name: Mosier Well No. H-2

Location: SW-NE-NE Sec. 4 Twp. 9 Rge. (E)(W) 27

County: Sheridan Total Depth 3952 Oil Well

Gas Well  Input Well  SWD Well  D & A X Lost Hole

Mr. Rowe was instructed to plug the well as follows:

220'--8 5/8" Surface pipe, cement circulated with 175 Sx.  
Top of Dakota section @ 1060'.

Circulate hole with heavy mud. Pull DP to 1300' and displace 100 Sx.  
cement thru DP. Pull DP to 245' and displace 20 Sx. cement thru DP.  
Pull DP, set bridge @ 40' with 1/2 sack hulls and 10 Sx. cement to bottom  
of cellar.

RECEIVED  
STATE CORPORATION COMMISSION

AUG 13 1968  
CONSERVATION DIVISION  
Wichita, Kansas

0813-1968

Very truly yours,

M. S. Nichols  
Conservation Division Agent