



State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS 67202

VERBAL PERMIT FORM (To Be Filed By Plugging Agent)

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

05-07-1970
RECEIVED
STATE CORPORATION COMMISSION
MAY 7 1970
CONSERVATION DIVISION
Wichita, Kansas

15-179-20249-00-00

Dear Sir:

Mr. Bill Rowe of Slawson Drlg. Co., Inc., has this date requested permission to plug the following described well:

Mr. Rowe guarantees payment of the plugging fee.

Operator's full Name: Donald C. Slawson,

Complete Address: 408 One-Twenty Building, Wichita, Kansas.

Lease Name: Mosier Well No. H-3

Location: SE-SE-NE Sec. 4 Twp. 9 Rge. (E)(W) 27

County: Sheridan Total Depth 3985 Oil Well

Gas Well Input Well SWD Well D & A X Lost Hole

Mr. Rowe was instructed to plug the well as follows:

225'--8 5/8" Surface casing, cement circulated with 200 Sx.
Top of Dakota section @ 1100'.

Circulate hole with heavy mud. Pull DP to 1325' and displace 100 Sx.
cement thru DP. Pull DP to 250' and displace 25 Sx. cement thru DP.
Pull DP, set bridge @ 40' with 1/2 sack hulls and 10 Sx. cement to bottom
of cellar.

Very truly yours,

Conservation Division Agent