

State of Kansas



ROBERT B. DOCKING Governor
 DALE E. SAFFELS Chairman
 JULES V. DOTY Commissioner
 JAMES O. GREENLEAF Commissioner
 RAYMOND B. HARVEY Secretary
 JACK GLAVES Gen. Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

500 Insurance Bldg.

212 N. Market

WICHITA, KANSAS 67202

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

15-179-20187-00-00

RECEIVED
 STATE CORPORATION COMMISSION
 FEB 26 1969
 CONSERVATION DIVISION
 Wichita, Kansas

02-26-1969

J. Lewis Brock
 Administrator
 500 Insurance Building
 Wichita, Kansas 67202

Dear Sir:

Mr. Lyle Hicks of L. J. Dreiling & Sons, Inc., has this date requested permission to plug the following described well:

Mr. Hicks guarantees payment of the plugging fee.

Operator's full Name: Don E. Pratt,

Complete Address: Drawer "D", Hays, Kansas.

Lease Name: Kennedy ^{KCC} A 2AP Well No. 1

Location: SE-SE-NW Sec. 5 Twp. 9 Rge. (E)(W) 27

County: Sheridan Total Depth 4005' Oil Well

Gas Well Input Well SWD Well D & A X Lost Hole

Mr. Hicks was instructed to plug the well as follows:

266'--8 5/8" Surface casing, cement circulated with 200 Sx.
Top of Dakota section @ 960'.

Circulate hole with heavy mud. Pull DP to 1175' and displace 100 Sx, cement thru DP. Pull DP to 275' and displace 20 Sx. cement thru DP. Pull DP, set bridge @ 40' with 1/2 sack hulls and 10 Sx. cement to bottom of cellar.

Very truly yours,

Conservation Division Agent